

The delivery is made by a crane-lorry who will get the main package as close as the driver considers to be properly safe and practical.

The actual position will depend on the configuration of your access, your driveway surface & slopes, overhead cables & trees etc; if access is restricted, it is often necessary to unload to the roadside.

He will unload the Sauna as one palletised load (exactly as it left the factory in Finland) together with some smaller boxes containing the Stove and Accessories, etc.

As detailed on the Sylva 4 page:

Main Package Appx Dimensions:
4.2 x 1.1 x 1.1 metres; 1.6 tonnes appx.
(This also with a number of smaller packages)

When opened, the individual parts inside the main package are all capable of being carried by hand to the final assembly site.

Most parts are individual logs or planks, as against large made-up sections. (The sauna ceiling is the only 'sectional' part)

Some parts (e.g. the doors) are quite bulky and heavy, so two able-bodied people will be needed to carry them to the final assembly site.